



ALL MATERIAL PVC SDR 35 ASTM 3034
 NOTIFY TOWN OF MIDDLETOWN 48 HOURS IN ADVANCE OF CUT IN.
 CONTRACTOR IS RESPONSIBLE FOR DIVERSIONS, BYPASS PUMPING AND CLEAN UP OF SEWAGE SPILLS.
 FOLLOW TRENCH BACKFILL REQUIREMENTS

FERNCO ADAPTORS
 6" CL X PVC 1002-66 CI X PVC 1056-66
 8" CL X PVC 1002-88 CI X PVC 1056-88

TOWN OF MIDDLETOWN APPROVED: _____ DATE 06-01-01	STANDARD DETAIL	REVISIONS:	S-4
	CUT IN WYE FOR EXISTING SS MAINS	01/8/08	